

Ground Bond Connections

Cable, Clamp, Magnetic Connection, Clip

		Ground Bond Test Cable		
		ST 05-I	ST 05-L	ST 05-F
		High-current plug (ST 04-i) and free cable ends	Banana plug (4 mm 0.6 in)	Free cable ends on both sides
Description		Cable for high currents		
Max. Operating Voltage	DC Voltage	1500 VDC		
Test Voltage	Contour / Connection	1500 VDC		
	Connection / Start Switch	1500 VDC		
Cable lengths		2 m 6.6 ft, 5 m 16.4 ft, 10 m 32.8 ft, 15 m 49.2 ft		

		Ground Bond Clamp		
		KL 01-I	KL 01-L	KL 01-F
		High-current plug (ST 04-i)	Banana plug (4 mm 0.6 in)	Free cable ends
Description		Heavy-duty clamping pliers for the ground bond connection on the housing		
Max. Operating Voltage	DC Voltage	1500 VDC		
Test Voltage	Contour / Connection	1500 VDC		
	Connection / Start Switch	1500 VDC		
Cable lengths		2 m 6.6 ft, 5 m 16.4 ft, 10 m 32.8 ft, 15 m 49.2 ft		

		Magnetic PE Conductor Connection		
		PE 25-I	PE 25-L	PE 25-F
		High-current plug (ST 04-i)	Banana plug (4 mm 0.6 in)	Free cable ends
Description		Magnetic ground bond connection on the housing		
Max. Operating Voltage	DC Voltage	1500 VDC		
Test Voltage	Contour / Connection	1500 VDC		
	Connection / Start Switch	1500 VDC		
Cable lengths		2 m 6.6 ft, 5 m 16.4 ft, 10 m 32.8 ft, 15 m 49.2 ft		

		Crocodile Clip		
		KL 89-I	KL 89-L	KL 89-F
		High-current plug (ST 04-i)	Banana plug (4 mm 0.6 in)	Free cable ends
Description		Crocodile clip for connection to the DUT		
Max. Operating Voltage	DC Voltage	1500 VDC		
Test Voltage	Contour / Connection	1500 VDC		
	Connection / Start Switch	1500 VDC		
Cable lengths		2 m 6.6 ft, 5 m 16.4 ft, 10 m 32.8 ft, 15 m 49.2 ft		

		Kelvin Clamp		
		KL 90-I	KL 90-L	KL 90-F
		High-current plug (ST 04-i)	Banana plug (4 mm 0.6 in)	Free cable ends
Description		Kelvin clamp for connection to the DUT		
Max. Operating Voltage	DC Voltage	1500 VDC		
Test Voltage	Contour / Connection	1500 VDC		
	Connection / Start Switch	1500 VDC		
Cable lengths		2 m 6.6 ft, 5 m 16.4 ft, 10 m 32.8 ft, 15 m 49.2 ft		